B-15(A)

TENDER FORM/N.I.T

Form for supply & construction of **Air compressor room civil work**
Email: bhogpurcsm@gmail.com Mill web site: - www.bhogpurcsm.com

The General Manager
The Bhogpur Coop Sugar Mills Ltd.,
Bhogpur (Jalandhar)
Sub: - supply & construction of **Air compressor room civil work**
In response to above reference, I/we hereby quote my/our lowest rates for the following items subject to the mills terms & conditions overleaf.

Sr. No.	Description of material	Unit	Qty. Aprrox.	Rates Quoted
1.	First class burnt brick work laid in cement sand mortar 1:5 in first story upto 4 meters above to plinth	Cum	8.75	
2.	Providing and laying in reinforced cement concrete M-20 mechanically batch mixed using batch type concrete mixer as per IS: 1791 and vibrated by needle vibrator but excluding steel reinforcement centring and shuttering in superstructure.	Cum	7.15	
3.	Providing centring and shuttering removal of form work using waterproof ply shuttering for R.C.C columns, beams, walls, fascias etc. and good condition steel plates for suspended floors, roofs, landings, etc. for:	Sqm	50.00	
4.	Providing and laying Steel reinforcement, cold twisted deforming bars Fe 500 grade for all R.C.C works ,including bending,binding and placing in position complete.	Qtls	5.70	
5.	CEMENT PLASTER 12.5 mm thick cement plaster 1:3	Sqm	94.00	

Note- Actual measurement will be made after the completion of work.

J.E (CIVIL)

C.E

THE BHOGPUR COOP. SUGAR MILLS LTD; BHOGPUR

Terms and conditions:

1. Last date of receipt of tender is 19.06.2020 upto 5PM
2. The Press Tender should be submitted in the Prescribed NIT in the sealed envelope,
3. Negotiations, if required will be done with the lowest tendered
4. Payment term will be decided at the time of negotiation.
5. If you leave the work during contract, the Management shall be at liberty to make alternative arrangement at your risk and cost.
6. GST and any other taxes shall be extra as applicable.
7. Responsibility of PF of your labour completely in your scope.
8. The Contractor will get adequate insurance cover of the labour employed by him in the mills which will be shown to CE/Factory Manager before their entry In mills.
9. The contractor shall have abide by rules and regulations of the mills and shall be responsible for all govt. rules and regulations with regard to the labour engaged by him. In case of occurrence of accident etc., will be fully responsible for total compensation, medical treatment etc. of the labour so engaged by by him.
10. Any damage done to mill property during the working by your workers or you it shall be recovered from you after accessing the damage by concerned HOD.
11. TDS if any shall be deducted as per rule.
12. Provident fund of contractor labour shall be responsibility of the contractor.
13. Required man power will be arranged by you as per direction of HOD otherwise undersigned reserve the right to engage additional man power on your cost and risk.
14. Undersigned reserve the right to cancel your contract any time without assigning any reasons.

General Manager

B-15(B)

TENDER FORM/N.I.T

Form for supply & construction of **VARIOUS CIVIL WORK IN SUGAR PLANT**
Email: bhogpurcsm@gmail.com Mill web site: - www.bhogpurcsm.com

The General Manager
The Bhogpur Coop Sugar Mills Ltd.,
Bhogpur (Jalandhar)
Sub: - supply & construction of **VARIOUS CIVIL WORK IN SUGAR PLANT**

In response to above reference, I/we hereby quote my/our lowest rates for the following items subject to the mills terms & conditions overleaf.

Sr. No.	Description of material	Unit	Qty. Aprrox.	Rates Quoted
1.	supply of good earth (for leveling course)including watering & compacted by road roller as per PWD specification	Cum	750.00	
2.	Granular sub base-1 construction of GSB 150mm thick by providing coarse graded material grading-1,spreading in uniform layers with motor grader on prepared surface and compacting with road roller as per CSR 24.8	Cum	131.27	

Note- Actual measurement will be made after the completion of work.

J.E(civil)

C.E

THE BHOGPUR COOP. SUGAR MILLS LTD; BHOGPUR

Terms and conditions:

1. Last date of receipt of tender is 19.06.2026 upto 5PM.
2. The Press Tender should be submitted in the Prescribed NIT in the sealed envelope,
3. Negotiations, if required will be done with the lowest tendered
4. Payment term will be decided at the time of negotiation.
5. If you leave the work during contract, the Management shall be at liberty to make alternative arrangement at your risk and cost.
6. GST and any other taxes shall be extra as applicable.
7. Responsibility of PF of your labour completely in your scope.
8. The Contractor will get adequate insurance cover of the labour employed by him in the mills which will be shown to CE/Factory Manager before their entry In mills.
9. The contractor shall have abide by rules and regulations of the mills and shall be responsible for all govt. rules and regulations with regard to the labour engaged by him. In case of occurrence of accident etc., will be fully responsible for total compensation, medical treatment etc. of the labour so engaged by by him.
10. Any damage done to mill property during the working by your workers or you it shall be recovered from you after accessing the damage by concerned HOD.
11. TDS if any shall be deducted as per rule.
12. Provident fund of contractor labour shall be responsibility of the contractor.
13. Required man power will be arranged by you as per direction of HOD otherwise undersigned reserve the right to engage additional man power on your cost and risk.
14. Undersigned reserve the right to cancel your contract any time without assigning any reasons.

General Manager

TENDER FORM/N.I.T

B-15 (c)

Form for supply & construction of **VARIOUS CIVIL WORK IN SUGAR PLANT**
Email: bhogpurcsm@gmail.com Mill web site: - www.bhogpurcsm.com

The General Manager
The Bhogpur Coop Sugar Mills Ltd.,
Bhogpur (Jalandhar)
Sub: - supply & construction of **VARIOUS CIVIL WORK IN SUGAR PLANT**

In response to above reference, I/we hereby quote my/our lowest rates for the following items subject to the mills terms & conditions overleaf.

Sr. No.	Description of material	Unit	Qty. Aprrox.	Rates Quoted
1.	Excavations for column foundation in earth all kinds of soil. All excavation operations manually or mechanically shall include excavation, dressing of sides, ramming of bottoms, lift upto 2 Mtr., stacking the material temporarily near the excavated area. Cost will also include filling back excavated earth in trenches, plinth, sides of foundations, footings etc. in layers not exceeding 20 cm. in depth, consolidating each deposited layer with rammer, plate vibrator etc	Cum	5.00	
2.	Providing and laying 100 mm thick cement concrete 1:3:6 (1 cement 3 coarse sand 6 graded stone aggregate 40 mm. nominal size) in foundations, machine foundations, footings and bases of columns and under floors including the cost of centering and shuttering	Cum	5.00	
3.	Providing and fixing Cold twisted deformed (Ribbed/ Tor steel Bar) Bars Fe 500 grade for R.C.C works in columns and beam, where not including in the complete rate of RCC including bending and placing in position complete.	Qtls	15.40	
4.	Providing centring and shuttering removal of form work using waterproof ply shuttering for R.C.C columns, beams, walls, fascias etc. and good condition steel plates for suspended	Sqm	55.00	
5.	Providing and laying in reinforced cement concrete M-20 mechanically batch mixed using batch type concrete mixer as per IS: 1791 and vibrated by needle vibrator but excluding steel reinforcement centring and shuttering in foundation and plinth.	Cum	18.00	

Note- Actual measurement will be made after the completion of work.

J.E(civil)

C.E

B-15 (L)

THE BHOGPUR COOP. SUGAR MILLS LTD; BHOGPUR

Terms and conditions:

1. Last date of receipt of tender is 19.06.2026 upto 5PM.
2. The Press Tender should be submitted in the Prescribed NIT in the sealed envelope,
3. Negotiations, if required will be done with the lowest tendered
4. Payment term will be decided at the time of negotiation.
5. If you leave the work during contract, the Management shall be at liberty to make alternative arrangement at your risk and cost.
6. GST and any other taxes shall be extra as applicable.
7. Responsibility of PF of your labour completely in your scope.
8. The Contractor will get adequate insurance cover of the labour employed by him in the mills which will be shown to CE/Factory Manager before their entry In mills.
9. The contractor shall have abide by rules and regulations of the mills and shall be responsible for all govt. rules and regulations with regard to the labour engaged by him. In case of occurrence of accident etc., will be fully responsible for total compensation, medical treatment etc. of the labour so engaged by by him.
10. Any damage done to mill property during the working by your workers or you it shall be recovered from you after accessing the damage by concerned HOD.
11. TDS if any shall be deducted as per rule.
12. Provident fund of contractor labour shall be responsibility of the contractor.
13. Required man power will be arranged by you as per direction of HOD otherwise undersigned reserve the right to engage additional man power on your cost and risk.
14. Undersigned reserve the right to cancel your contract any time without assigning any reasons.

General Manager

B-15 (D)

TENDER FORM/N.I.T

Form for supply & construction of **VARIOUS CIVIL WORK IN SUGAR PLANT**
Email: bhogpurcsm@gmail.com Mill web site: - www.bhogpurcsm.com

The General Manager
The Bhogpur Coop Sugar Mills Ltd.,
Bhogpur (Jalandhar)
Sub: - supply & construction of **VARIOUS CIVIL WORK IN SUGAR PLANT**

In response to above reference, I/we hereby quote my/our lowest rates for the following items subject to the mills terms & conditions overleaf.

Sr. No.	Description of material	Unit	Qty. Aprrox.	Rates Quoted
1.	Supply and laying of first class burnt brick work in cement sand mortar 1:5 in first storey up to 4 metres above plinth level.	Cum	62.00	
2.	Supply of material and plaster work 12.5 mm thick cement and sand - 1:4 ratio	Sqm	220.00	
3.	Laying 80mm thick factory made cement concrete interlocking paving blocks of M-40 grade manufactured as per IRC SP 63-2014 and of approved size and design/shape laid in ordinary grey colour and pattern over and including 40mm thick compacted bed of coarse sand, filling the joints with fine sand etc as per CSR 14.139	Sqm	895.00	

Note- Actual measurement will be made after the completion of work.

J.E(civil)

C.E

THE BHOGPUR COOP. SUGAR MILLS LTD; BHOGPUR

Terms and conditions:

1. Last date of receipt of tender is 19.06.2026 up to 5PM.
2. The Press Tender should be submitted in the Prescribed NIT in the sealed envelope,
3. Negotiations, if required will be done with the lowest tendered
4. Payment term will be decided at the time of negotiation.
5. If you leave the work during contract, the Management shall be at liberty to make alternative arrangement at your risk and cost.
6. GST and any other taxes shall be extra as applicable.
7. Responsibility of PF of your labour completely in your scope.
8. The Contractor will get adequate insurance cover of the labour employed by him in the mills which will be shown to CE/Factory Manager before their entry In mills.
9. The contractor shall have abide by rules and regulations of the mills and shall be responsible for all govt. rules and regulations with regard to the labour engaged by him. In case of occurrence of accident etc., will be fully responsible for total compensation, medical treatment etc. of the labour so engaged by by him.
10. Any damage done to mill property during the working by your workers or you it shall be recovered from you after accessing the damage by concerned HOD.
11. TDS if any shall be deducted as per rule.
12. Provident fund of contractor labour shall be responsibility of the contractor.
13. Required man power will be arranged by you as per direction of HOD otherwise undersigned reserve the right to engage additional man power on your cost and risk.
14. Undersigned reserve the right to cancel your contract any time without assigning any reasons.

General Manager